Lifting Solutions Group
Axel Johnson International

# Wire Rope Lifting Sling WLS-275

## Product information



**Standard steel wire rope construction: 6x36WS IWRC, 1960N/mm2**
**Design:** Master link in one end and eyehooks with safety latch in other ends, aluminum ferrule secured (mechanical spliced).

Load table at Technical Data -> Show table

Please specify the needed (working) length with your request.

Other rope construction and/or end-terminations such as top rings, shackles, hooks, etc.. possible on request. In that case, please contact us to discuss the possible options or specify it with your request.

... *Read more*

**Certex Lietuva UAB**
info@certex.lt
+370 5 2300020

© November 2026 - All Rights Reserved

Lifting Solutions Group
Axel Johnson International

# Wire Rope Lifting Sling WLS-275

## Technical data

| Part code | Diameter mm | WLL ton | WLL 0-45° t | WLL 45-60° t |
|---|---|---|---|---|
| 1605 | 3 | 0.16 | 0.16 | 0.12 |
| 1605 | 4 | 0.29 | 0.29 | 0.21 |
| 1605 | 5 | 0.45 | 0.45 | 0.32 |
| 1605 | 6 | 0.66 | 0.66 | 0.47 |
| 1605 | 7 | 0.89 | 0.89 | 0.64 |
| 1605 | 8 | 1.15 | 1.15 | 0.82 |
| 1605 | 9 | 1.45 | 1.45 | 1.04 |
| 1605 | 10 | 1.79 | 1.79 | 1.28 |
| 1605 | 11 | 2.17 | 2.17 | 1.55 |
| 1605 | 12 | 2.57 | 2.57 | 1.84 |
| 1605 | 13 | 3.03 | 3.03 | 2.17 |
| 1605 | 14 | 3.52 | 3.52 | 2.51 |
| 1605 | 16 | 4.6 | 4.6 | 3.3 |
| 1605 | 18 | 5.81 | 5.81 | 4.1 |
| 1605 | 20 | 7.17 | 7.17 | 5.1 |
| 1605 | 22 | 8.69 | 8.69 | 6.2 |
| 1605 | 24 | 10.33 | 10.33 | 7.38 |
| 1605 | 26 | 12.13 | 12.13 | 8.66 |
| 1605 | 28 | 14.06 | 14.06 | 10.04 |
| 1605 | 32 | 18.37 | 18.37 | 13.12 |
| 1605 | 36 | 23.23 | 23.23 | 16.59 |
| 1605 | 40 | 28.78 | 28.78 | 20.56 |
| 1605 | 44 | 34.69 | 34.69 | 24.78 |
| 1605 | 48 | 41.37 | 41.37 | 29.55 |

**Certex Lietuva UAB**
info@certex.lt
+370 5 2300020

© November 2026 - All Rights Reserved